

Open tender for Supply & supervision of Prewired metering panel at OPTCL Grid 33KV feeder.				
Tender Enq.:- TPCODL/P&S/1000001509/2024-25				Date:-23.12.2024
Sub: Reply of prebid query				
SL No.	Clause No. & Name	Description	BPSPL Queries	TPCODL REPLY
1	1.1 Scope of Work	wiring from VCB panel to metering panel	Please specify the distance b/w both panels	Installation under TPCODL scope , corrigendum issued for Supply & supervision of metering Panel only with revised Boq , Specification.
2	NIL	NIL	Please clarify the metering panel is compartmentised or Non-Compartmentised	Metering Panel will be Non- Compartmentised
3	5.1 , page no-14	Panel enclosure shall comply with IP 54 for Indoor installation	Pls. Confirm the IP-54 configuration. It is double (Inner door & Outer Door) with Canopy or single door with canopy.	Indoor application : requirement of IP-54 Class only & for Outdoor application IP- 55 Class with extra top Canopy. 1.Provision of smart meter fixing inside panel to be provided. 2.For each section i.e. TB section in both side of Metering section and Metering section itself . and Single door is required with proper locking and sealing arrangement.
4	5.1 , page no-14 & 15	Type Test report for the same shall be submitted by the Bidder with the bid itself which shall be within 5 years from bid Submission date	Is Fresh Type Test is required for the IP-55 or, consider our existing report for IP	For Indoor : IP54 and For Outdoor : IP 55 is required. Note : If Type test report is already available for the said dimension or nearer to the same ,then fresh test is not required.