

Ref: TPCODL/P&S/1000007846/2025-26/Corrigendum/001

Dated: 31st January 2026

CORRIGENDUM-1

Open tender number TPCODL/P&S/100007846/2025-26 for SITC of 5Tonne gantry crane at DT Workshops of TPCODL

With reference to above, the bidders are intimated to note the followings:

I. Modification in Annexure-II(Technical Specification):

TECHNICAL SPECIFICATIONS OF SINGLE GIRDER GANTRY CRANE (FLOOR MOVABLE) -- CAPACITY 05 MT			
Sl. No.	DESCRIPTION	PREVIOUS SPEC.	PROPOSED SPEC.
01.	CAPACITY SAFE WORKING LOAD:	5 TON	NO CHANGE
02.	HEIGHT OF LIFT:	2.8 Meter	2.5 to 2.8 METER
03.	SPAN:	9.5 Meter	9.0 to 9.5 METER
04.	CLASS & DUTY:	CLASS-II (M5) as per IS 3177	NO CHANGE
05.	OPERATION:	Wireless remote	NO CHANGE
06.	LOCATION:	Indoor	NO CHANGE
07.	HOISTING Chain. (MAIN HOIST)		
a.	DIAMETER:	MH- 10 mm, Make-Indef.	NO CHANGE
c.	NUMBER OF FALLS: MH: -	2 fall	NO CHANGE
08.	OPERATION SPEED.		
a.	MAIN HOIST:	04 mpm with VFD	NO CHANGE
b.	CROSS TRAVEL:	10 mpm with VFD	NO CHANGE
c.	LONG TRAVEL:	15 mpm with VFD	NO CHANGE
09.	MOTORS.		
a.	MAIN HOIST (Sq cage):	3.5kW / 6.0Hp	4.5kW / 6.0Hp
b.	CROSS TRAVEL (Sq. cage):	0.37kW / 0.5Hp	NO CHANGE

c. LONG TRAVEL (Sq cage):	1.2kW /1.5Hp	1.1kW / 1.5Hp
10. WHEELS.		
a. LONG TRAVEL:	Dia-200 mm & Qty: - 4 (EN-9 FORGED)	NO CHANGE
b. CROSS TRAVEL:	Dia-140 mm & Qty-4 (EN-9 FORGED)	Dia-140mm & Qty-4 (EN-9/EN-8 FORGED)
11. RAIL		
a. LONG TRAVEL: FLOOR	SQ BAR 40	SQ BAR 40 OR 30LB/YARD ON THE
12 HOOKS: -	Drop forged, C- type swiveling on thrust thrust bearing bearing as per IS:3815	Drop forged, C- type swiveling on INDEF Standard.
13. HOIST WEIGHT:	0.3 Ton (Approximately)	NO CHANGE
14. CRANE WEIGHT:	2.5 Ton (Approximately)	NO CHANGE
15. MAIN BRIDGE GIRDER:	350X350 BOX TYPE FABRICATED STRUCTURE IS as per IS 2062	BOX TYPE FABRICATED STRUCTURE as per as per IS 3177.
16. END CARRIAGES:	Box Fabricated / ISMC	NO CHANGE
17. POWER SUPPLY:	415 V +/-10% A.C, 3- Phase + 1 ground	NO CHANGE
18. DSL BUS BAR:	(R, Y, B, G) 4 Way type, 125 Amp	(R, Y, B, G) 4 Way type, 125 Amp OF 11.0 METER BAY LENGTH

Additional point added

01. The radio remote shall have emergency push bottom, start, stop, forward, reverse, up, down, hooter, left & right operation.
02. All motion shall be provided with VFD.
03. Transportation of gantry crane along with loose materials (bus bar, square bar/rail pole to site) will be in vender scope.



04. Installation & commissioning of the crane along with rail/square bar will be in vendor scope.

II. Revisions has been made for below mentioned Clause 1.3 Calendar of Events.

S. No.	Description	Existing Timeline	Revised Timeline
(a)	Last date and time of receipt of Bids	31.01.2026; 15:00 Hours	06.02.2026; 15:00 Hours

All other terms and conditions of the above tender will remain same.

By Order
Chief Operating Officer